

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of the Work: Road Development and Asphaltting Works at Ganesha Layout Cross Roads Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.


Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	531.38	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	75.60	
2	405.56	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	105.84	
3	888.30	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	58.32	
4	888.30	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	75.60	
5	503.36	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1438.56	
6	2866.90	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	12.20	
7	2866.90	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	74.52	

No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	67.59	Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (25-30mm) with 5% CRMB-55 grade , etc complete as per specifications and directions of engineer in charge of the work	Cum	11070.00	
9	749.55	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. etc complete as per specifications and directions of engineer in charge of the work	Cum	73.57	

Signature of the Contractor


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಬೆಂದರ್ ಪದ್ಧತಿಗಾಗಿ
ಶಿಕ್ಷಣದಿಗಲ ಸಂಖ್ಯೆ 1017
ಶಿಕ್ಷಣದಿ ಮಾಡಿ/ಇಲ್ಲದ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿರೆ


Superintending Engineer
Yelahanka Zone
BBMP, Bangalore - 92